

SURVEY & REMONUMENTATION

APR 14 1998

LIBER

2 PAGE 179

RECEIVED FOR RECORD

97 DEC -2 AM 9:10

LIBER NO. 2 PAGE NO. 179
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

REMONUMENTATION SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in CUSTER TOWNSHIP

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R14E	E - 4
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY & REMONUMENTATION

JAN 08 1998

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on July 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E - 4

GLO Notes

Set 1/4 Section Post
Cedar 10 S40°E 21
Birch 18 N87°E 17

Old Survey Liber, surveys dated March 1894
by Galbraith, survey dated April 1895 by Ward
Act 74 None
Act 132 Liber 4 Page 112

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 4

E 1/4 Corner Section 8 T12N-R14E Custer Twp.
Found Monu Box in place with 5/8" Iron Bar

APPROVED PEER BOARD MEETING
NOV. 26, 1997 *JM*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 4

E 1/4 Corner Section 8 T12N-R14E Custer Twp.
West 50.60 feet to a nail in a Power Pole
N80°E 32.10 feet to top center of a culvert
S45°E 46.69 feet to top center of a culvert
South 2662.00 feet to the SE Corner Section 8
North 2664.70 feet to the NE Corner Section 8



Signed by *John A Milletics*
Surveyor's Michigan License No. 25859

Date Nov 12, 1997