SURVEY & REMONUMENTATION

APR 1 4 1998

SEGNION ATION

LIBER 2 FAGE 180

LAND CORNER RECORDATION CERTIFICATE

RECEIVED FOR RECORD

	7	. 1				
97	DEC	-2	ΔM	Q:	1	l

IBER NO 2 PAGE NO 180

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SURVEY & REMONUMENTATION

JAN 0 8 1998

SECTION


Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, <u>John A Milletics</u>, in a field survey on <u>July 21</u>, 19 <u>97</u> do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.



A. Description of original monument and accessories and/or subsequent restoration:

E - 5

GLO Notes

Set Post Corner
B. Ash 12 N07°W 7
Hemlock 10 S07°E 10

Old Survey Liber, surveys dated March 1894 by Galbraith, survey dated April 1895 by Ward, survey dated Dec. 1896 by Ward

Act 74 None

Act 132 Liber 4 Page 54

Liber 4 Page 474

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 5

Found Monu Box with 5/8" iron bar

APPROVED PEER BOARD MEETING NOV. 26, 1997

C. Description of monument for corner and accessories established to perpetuate	te locating the position of the corner:
E - 5	
NE Cor Section 17 T12N-R14E Custer Twp.	1111 210 . 00
Monu Box in place with 5/8" iron bar	
N40°W 78.73 feet to a nail in a Power Pole	
N45°E 43.94 feet to a stop sign	John A. Milletics The Land Surveyor
S45°E 54.50 feet to a cement pillar	No. 25889 \$
S45°W 73.50 feet to a nail in a Power Pole	= 0:
S70°W 41.82 feet to a stop sign	The state of the s
South 2675.64 feet to the E 1/4 Corner Section 17	The Second of the Second
North 2662.00 feet to the E 1/4 Corner Section 8	
Signed by	Date Nov 12, 1997
Surveyor's Michigan License No. 25859	