

SURVEY & REMONUMENTATION

APR 14 1998

LIBER 2 PAGE 184

RECEIVED FOR RECORD

REMONUMENTATION SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

97 DEC -2 AM 9:11
LIBER NO. 12 PAGE NO. 184

For corners in CUSTER TOWNSHIP

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T 12NR14E	E - 9
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN
SURVEY & REMONUMENTATION

JAN 08 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on July 14, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E - 9
 GLO Notes
 Set Post Corner
 B. Ash 10 N80°W 24
 Birch 6 N32°E 18

Old Survey Liber, Surveys by Galbrith Dated April 1894, Nicol Dated May 1902, Nicol Dated Aug 1906
 Act 74 None
 Act 132 Liber 2 Page 208,
 Liber 3 Page 621

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 9
Found Monu Box in place with 1" Iron Bar

APPROVED PEER BOARD MEETING
NOV. 26, 1997

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 9
 NE Corner Section 29 T12N-R14E Custer Twp.
 Monu Box in place with 1" Iron Bar
 N45°W 60.00 feet to a nail in a Power Pole
 N50°E 87.00 feet to a Telephone Riser Box
 S70°W 40.42 feet to a Stop Sign
 S45°W 71.75 feet to a nail in a Power Pole
 South 2664.00 feet to the E 1/4 Cor Section 29
 North 2672.80 feet to the E 1/4 Cor Section 20



Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Nov 12, 1997