

SEP 20 2000

RECEIVED FOR RECORD

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

00 JUN 13 AM 11:56

SECTION

For corners in

LIBER NO. 3 PAGE NO. 5
MICHELLE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12</u> NR <u>14</u> E	<u>G - 7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

2000

I, John A Milletics, in a field survey on March 29, 19~~99~~^{XX} do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes
B. Ash 10" S58°W 18 Links
B. Ash 9" N84°E 16 Links
Old Survey Liber M.E. Ward - Dec 1896
L.C.R.C. - None
Act 132 - None
Unrecorded Survey - Milletics April 1986, Milletics Jan 1991, Milletics Oct 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 7
SE Corner Section 16
Found 1/2" Iron Bar in gravel Road Bed
West 2657.48 feet to the S 1/4 Corner
East 2644.24 feet to the S 1/4 Corner
Accepted as best evidence



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 7
SE Corner Section 16
1/2" Iron Bar in gravel Road Bed with cap
N45°E 41.80 feet to a Stop Sign
N50°E 92.00 feet to the SW Corner of a Building
S45°E 69.20 feet to a Nail in a Wooden Fence Post
S45°W 72.30 feet to a nail in a Power Pole
S75°W 34.20 feet to a Stop Sign
West 2657.48 feet to the S 1/4 Corner
East 2644.24 feet to the S 1/4 Corner

APPROVED PEER BOARD
MEETING JUNE 12, 2000

gm

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date May 8, 2000