

SEP 26 2000

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

00 JUN 13 AM 11:56

LIBER NO. 3 PAGE NO. 6
NICHELE VANNORMAN
REGISTER OF DEEDS
SANDY AC CO., MICHIGAN

SECTION

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T12NR14E	H - 7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			
3												
4	7		8		9		10		11			12
5												
6	10		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

John A Milletics, in a field survey on March 29, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

- Birch 10" S87°W 11 Links
- Beech 10" N87°E 20 Links

Old Survey Liber - None
Act 132 - None

Unrecorded Surveys - Milletics Oct 1991 - Milletics Dec 1991

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 7

N 1/4 Corner Section 22

Found 1/2" Iron Bar in Gravel Road Bed
West 2644.24 feet to the NW Corner
East 2658.60 feet to the NE Corner
Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 7

N 1/4 Corner Section 22 T12N-R14E

1/2" Iron Bar in Gravel Road Bed with Cap

N10°W 34.95 feet to a Stop Sign

N30°W 34.60 feet to the SE Corner of a Bell Riser Box

s45°E 77.15 feet to a Nail in a Power Pole

S30°E 34.35 feet to a Stop Sign

S45°W 74.15 feet to a Nail in a Power Pole

West 2644.24 feet to the NW Corner

East 2658.60 feet to the NE Corner

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date May 8, 2000

APPROVED PEER BOARD
MEETING JUNE 12, 2000

JA