

SEP 20 2000

LIBER 3 PAGE 7

RECEIVED FOR RECORD

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUN 13 AM 11:57

SECTION

For corners in

Sanilac
(County)

Located in:

Corner Code #

- 1. Public Land Survey T12N R14E I - 7
- T R
- T R
- T R
- 2. Property Controlling in Section S T R
- S T R
- 3. Miscellaneous Property in Sec. S T R
- S T R

LIBER NO. 3 PAGE NO. 7
NICHELE YANNORMAN
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A Milletics, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

- W. Oak 30" S30°W 18 Links
- W. Oak 30" N43°E 27 Links

Old Survey Liber - None

Act 132 - Liber 4 Page 593 Milletics July 1982

Unrecorded Survey - Milletics Oct 1991

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 7

NE Corner Section 22 T12N-R14E

Found 1/2" Iron Bar in Gravel Road Bed

West 2658.60 feet to the N 1/4 Corner

East 2666.66 feet to the N 1/4 Corner

Accepted as best evidence



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 7

NE Corner Section 22 T12N-R14E

1/2" Iron Bar in Gravel Road Bed with Cap

S60°W 34.10 feet to a Stop Sign

N40°W 36.45 feet to the West end of a 18" CMP

N30°E 69.35 feet to a nail in a 24" Oak

N40°E 41.30 feet to the SW Corner of a Bell Riser Box

West 2658.60 feet to the N 1/4 Corner

East 2666.66 feet to the N 1/4 Corner

APPROVED PEER BOARD
MEETING JUNE 12, 2000

jm

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date May 8, 2000