

SEP 20 2000

LIBER 3 PAGE 9

RECEIVED FOR RECORD

00 JUN 13 AM 11:57

LIBER NO. 3 PAGE NO. 9  
MICHELE VANORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

2000 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R14E	K - 7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

2000

I, John A Milletics, in a field survey on March 29, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

K - 7  
GLO Notes  
Lynn 8" S50°E 29 Links  
Lynn 6" S20°W 15 Links  
Old Survey Liber M.E. Ward April 1896  
Act 132 - None  
Unrecorded Survey - Sanilac Land 1980 - Milletics June 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K - 7  
NW Corner Section 24 T12N-R14E  
Found 1" Iron Bar in gravel Road Bed  
West 2666.66 feet to the N 1/4 Corner  
East 2657.30 feet to the N 1/4 Corner  
Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 7  
NW Corner Section 24 T12N-R14E  
1" Iron Bar in Gravel Road Bed  
N45°E 37.30 feet to a Stop Sign  
S45°E 58.70 feet to a nail in a Telephone Pole  
S20°E 80.75 feet to a nail in a 18" Pine Tree  
S45°W 34.70 feet to a Stop Sign  
N30°W 76.15 feet to a nail in a 12" Ash  
West 2666.66 feet to the N 1/4 Corner  
East 2657.30 feet to the N 1/4 Corner

APPROVED PEER BOARD  
MEETING JUNE 12, 2000

Signed by John A Milletics  
Surveyor's Michigan License No. 25859

Date May 8, 2000