

SEP 20 2000

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

00 JUN 13 AM 11:57

LIBER NO. 3 PAGE NO. 14
MICHELE VANHORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in SECTION

Sanilac

(County)

Located In:

Corner Code #

| | | |
|------------------------------------|-----------|-------|
| 1. Public Land Survey | T12N R15E | C - 7 |
| | T R | |
| | T R | |
| | T R | |
| 2. Property Controlling in Section | S T R | |
| | S T R | |
| 3. Miscellaneous Property in Sec. | S T R | |
| | S T R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on May 1 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|---|---|----|---|----|---|----|---|----|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

GLO NOTES

- Beech 18" N88°E 9 Links
- Beech 12" S 5°W 12 Links

OLD Survey Liber - None

Act 132 - Liber 3 Page 602 by Irvin Chope

Unrecorded Survey - Milletics Dated Feb 1994

L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 7

SW Corner Section 17 T12N-R15E

Found 1/2" Iron in Monu Box

West 2642.54 feet to the S 1/4 Corner

East 2632.80 feet to the S 1/4 Corner

Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 7

SW Corner Section 17 T12N-R15E

1/2" Iron Bar with cap in Monu. Box

N70°E 69.20 feet to the SW Corner of a Right of Way Marker

S70°W 40.64 feet to a Stop Sign

S65°E 58.22 feet to a nail in a Wooden Fence Post

N45°E 71.30 feet to a nail in a Power Pole

N50°W 68.10 feet to the SE Corner of a Riser Box

S50°W 46.00 feet to a nail in 30" Pine Tree

West 2642.54 feet to the S 1/4 Corner

East 2632.80 feet to the S 1/4 Corner

Signed by John A Milletics

Date June 3, 2000

Surveyor's Michigan License No. 25859

APPROVED PEER BOARD
MEETING JUNE 12, 2000

gm