

SEP 20 2000

RECEIVED FOR RECORD

2000 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

00 JUN 13 AM 11:57

SECTION  
For corners in

LIBER NO. 3 PAGE NO. 15  
NICHELE VANHORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

<u>Sanilac</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>15</u> E	<u>D - 7</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on May 1 <sup>2000</sup><sub>19</sub> do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

Beech 9" S9°E 6 Links  
Sugar 10' N3°E 12 Links

Old Survey Liber - None

Act 132 - Irvin Chope Liber 1 Page 155, Sanilac Land Liber 3 Page 779

Unrecorded Survey - Milletics Jan 1988

L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D - 7

S 1/4 Corner Section 17 T12N-R15E  
Found 1/2" Iron Bar in Gravel Road Bed  
West 2632.80 feet to the SW Corner  
East 2626.20 feet to the SE Corner  
Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 7

S 1/4 Corner Section 17 T12N-R15E  
Found 1/2" Iron Bar in Gravel Road Bed  
S55°W 56.70 feet to a nail in a 12" Ash Tree  
South 52.22 feet to a nail in a Power Pole  
North 31.30 feet to a nail in a Wooden Fence Post  
N50°W 56.35 feet to a nail in a 48" Ash Tree  
West 2632.80 feet to the SW Corner  
East 2626.20 feet to the SE Corner



APPROVED PEER BOARD  
MEETING JUNE 12, 2000

gm

Signed by John A Milletics  
Surveyor's Michigan License No. 25859

Date June 3, 2000