

SEP 20 2000

LIBER

3 PAGE 17

SECTION

2000 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

00 JUN 13 AM 11:58

For corners in

Sanilac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 12N R 15E F - 7

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

LIBER NO. 3 PAGE NO. 17  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on May 1, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

Sugar 14" S11°W 13 Links

Sugar 10" N49°W 19 Links

Old Survey Liber - None

Act 132 - Sanilac Land Survey Liber 3 Page 768

L.C.R.C. - None

Unrecorded survey - Milletics April 1986, Milletics 1999

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F - 7

S 1/4 Corner Section 16 T12N-R15E

Found no Iron - re set iron from previous surveys and witnesses

West 2644.94 feet to the SW Corner Section 16

East 2643.84 feet to the Se Corner Section 16

Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F - 7

S 1/4 Corner Section 16 T12N-R15E

1/2" Iron Bar in gravel Road Bed with cap

N05°W 49.15 feet to a nail in a 12' Ash

North 38.55 feet to a nail in a 18" Ash

S45°E 52.70 feet to a nail in a Power Pole

West 2644.94 feet to the SW Corner

East 2643.84 feet to the SE Corner

APPROVED PEER BOARD  
MEETING JUNE 12, 2000

*jm*

Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date June 3, 2000