

SEP 20 2000

LIBER 3 PAGE 22

2000 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

00 JUN 13 AM 11:58

LIBER NO. 3 PAGE NO. 22
MICHELE VANHORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SECTION

For corners in

Sanilac

(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------|-------|
| 1. Public Land Survey | T12N R15E | K - 7 |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| | T___ R___ | _____ |
| 2. Property Controlling in Section | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |
| 3. Miscellaneous Property in Sec. | S___ T___ R___ | _____ |
| | S___ T___ R___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

2000

I, John A Milletics, in a field survey on May 1, ~~1998~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

Beech 9" S86°E 13 Links

Beech 9" S85°W 6 Links

Act 132 - Irvin Chope Liber 2 Page 218

Irvin Chope Liber 3 Page 171

L.C.R.C - None

Unrecorded Surveys - Milletics Sept 1990, Milletics May 1993,

Milletics Sept 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K - 7

SW Corner Section 13 T12N-R15E

Found 1" Iron Bar in Gravel Road Bed

West 2646.12 feet to the S 1/4 Corner

East 2628.00 feet to the S 1/4 Corner

Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 7

SW Corner Section 13 T12N-R15E

1" Iron Bar in Gravel Road Bed

N30°W 39.50 feet to a Stop Sign

N30°E 85.06 feet to the SW Corner of a Bell Riser Box

S30°E 35.39 feet to a Stop Sign

S45°W 91.00 feet to a nail in a Power Pole

West 2646.12 feet to the S 1/4 Corner

East 2628.00 feet to the S 1/4 Corner

APPROVED PEER BOARD
MEETING JUNE 12, 2000

97

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date June 3, 2000