

SEP 20 2000

LIBER 3 PAGE 24

RECEIVED FOR RECORD

00 JUN 13 AM 11:58

LIBER NO. 3 PAGE NO. 24  
NICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

SECTION

2000 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T12N R15E	M - 7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on May 1, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

Hemlock 11" S38°W 38 Links  
Beech 6" N22°W 27 Links

L.C.R.C. Form - Dated 11-15-1999

Act 132 - Liber 3 Page 171

Unrecorded Surveys - Sanilac Land July 1980, Milletics Sept 1985  
Milletics Sept 1995, Milletics Oct 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 7

SE Corner Section 13 T12N-R15E

Found 1" Pipe in gravel road bed  
West 2665.68 feet to the S 1/4 Corner  
East 2606.82 feet to the S 1/4 Corner  
South 2666.00 feet to the E 1/4 Corner  
North 2649.50 feet to the E 1/4 Corner  
Accepted as best evidence



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 7

SE Corner Section 13 T12N-R15E

1" Iron Pipe in gravel road bed  
N45°W 41.67 feet to a nail in a 18" Ash Tree  
N30°W 67.03 feet to a nail in a Tele Pole  
N50°E 35.76 feet to a nail in a 30" Ash  
S40°E 46.90 feet to a Stop Sign  
S30°W 68.75 feet to a nail in a 36" Ash  
S45°W 71.00 feet to a nail in a Power Pole

APPROVED PEER BOARD  
MEETING JUNE 12, 2000

*gm*

Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date June 3, 2000