

JAN 19 2000

LIBER 2 PAGE 345

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

SECTION

For corners in

SANILAC

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 12N 16E A-2
 T R _____
 T R _____
 T R _____
- 2. Property Controlling S T R _____
 in Section S T R _____
- 3. Miscellaneous S T R _____
 Property in Sec. S T R _____

LIBER NO. 2 PAGE NO. 345
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-2 Beech 9 N17 1/2W 36; Beech 5 S18W 10 1/2
 Old Survey Liber - None
 Act 132 - None
 L.C.R.C. - None
 Unrecorded survey - Milletics Aug 1984 & Jan 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-2
 W 1/4 corner Section 6, T12N-R16E
 Found 1/2" Iron Bar in Gravel Road Bed
 North 2642.80 feet to the NW Corner Section 6
 South 2641.20 feet to the SW Corner Section 6
 Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 2
 W 1/4 Corner Section 6 T12N-R16E
 1/2" Iron Bar in gravel Road Bed with cap
 North 2642.80 feet to the NW Corner Section 6
 South 2641.20 feet to the SW Corner Section 6
 N15°E 131.15 feet to the SW Corner of a Bell Riser Box
 East 28.56 feet to a nail in a Fence Post
 East 33.00 feet to a 1/2" Iron Bar

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 11-15-1999