

JAN 19 2000

SECTION

LIBER 2 PAGE 346
1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 NOV 30 AM 9:06

LIBER NO. 2 PAGE NO. 346
NICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

SANILAC (County)	Located In:	Corner Code #
1. Public Land Survey	T 12N R 16E	A-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-3 Pine 48 S17W 14; Hemlock 9 N61E 18
Old Survey Liber - None
Act 132 - None
L.C.R.C. - None
Unrecorded survey - Milletics Dated Sept 1988

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3
SW Corner Section 6, T12N-R16E
Found 5/8" Iron bar in gravel Road Bed
North 2641.20 feet to the W 1/4 Corner
South 2653.30 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 3
SW Corner Section 6 T12N-R16E
5/8" Iron Bar in gravel Road Bed
North 2641.20 feet to the W 1/4 Corner
South 2653.30 feet to the W 1/4 Corner
N50°W 72.28 feet to a nail in a 18" Maple
N20°E 114.85 feet to the SW Corner of a Bell Riser Box
S45°W 35.35 feet to a Stop Sign
S45°E 51.39 feet to the NW Corner of a Bell Riser Box
N75°E 40.75 feet to a Stop Sign

Signed by John A. Milletics Date 11-15-1999
Surveyor's Michigan License No. 25859