

JAN 19 2000

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

SECTION

For corners in

LIBER NO. 2 PAGE NO. 348  
NICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO. MICHIGAN

SANILAC

(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 12NR 16E      A-5
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- T    R                    \_\_\_\_\_
- 2. Property Controlling    S    T    R                    \_\_\_\_\_
- in Section                S    T    R                    \_\_\_\_\_
- 3. Miscellaneous            S    T    R                    \_\_\_\_\_
- Property in Sec.         S    T    R                    \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- A-5 Beech 16 S52W 51 1/2; Beech 9 N53 1/2W 23
- Old Survey Liber - None
- Act 132 - Liber 1 Page 362, Liber 3 Page 39
- Unrecorded survey - Chope Dated Oct 1972 ,
- L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-5 SW Corner Section 7, T12N-R16E
- Found 5/8" Iron bar in Monu Box in pavement
- North 2648.00 to W 1/4 Corner
- South 2651.36 to W 1/4 Corner
- Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A - 5
- SW Corner Section 7 T12N-R16E
- 5/8" Iron Bar in Monu Box being 11.00 feet more less north of centerline
- N45°W 29.00 feet to a Stop Sign
- N40°E 59.40 feet to a Bell Riser Box
- N45°E 81.55 feet to a nail in a Power Pole
- S45°E 62.03 feet to the NW Corner of a Wooden Fence Post
- S45°W 70.00 feet to a nail in a Tele Pole
- North 2648.00 feet to the W 1/4 Corner
- South 2651.36 feet to the W 1/4 Corner

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date 11-15-1999