

JAN 19 2000

LIBER 2 PAGE 349

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 349
NICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>16</u> E	<u>A-6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-6 L1nn 28 S7W 36; Hemlock 8 N39W 24
Old Survey Liber - None
L.C.R.C. -None
Act 132 - Liber 1 Page 27 & Liber 1 Page 86
Unrecorded survey Dated July 1989 & Dated Aug 1986

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6
W 1/4 Corner Section 18, T12N-R16E
Found 1/2" Iron Bar in Gravel Road Bed 9' West of centerline
North 2651.36 feet to the NW Corner
South 2649.50 feet to the SW Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 6
W 1/4 Corner Section 18 T12N-R16E
1/2" Iron bar in gravel Road Bed with cap
North 2651.36 feet to the NW Corner
South 2649.50 feet to the SW Corner
East 33.00 feet to a 1/2" Iron
N70°W 22.68 feet to a nail in a 30" Ash
S45°W 21.60 feet to a nail in a 9" Ash
S60°E 31.71 feet to a nail in a 15" Ash

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date 11-15-1999