

JAN 19 2000

LIBER

2 PAGE 350

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

SECTION

For corners in

LIBER NO. 2 PAGE NO. 350  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO. MICHIGAN

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12</u> N R <u>16</u> E	<u>A-7</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 7, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	18			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

A. Description of original monument and accessories and/or subsequent restoration:

A-7 Hemlock 11 S38W 38; Beech 6 N22W 27  
Old Survey Liber - None  
L.C.R.C. - None  
Act 132 - None  
Unrecorded survey - Sanilac Land Dated July 1980, Milletics dated Sept 1985,  
Milletics Dated Sept 1995, Milletics Dated Oct 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7  
SW Corner Section 18, T12N-R16E  
Found 1" Pipe in gravel Road Bed  
North 2649.50 feet to the W 1/4 Corner  
South 2666.00 feet to the W 1/4 Corner  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 7  
SW Corner Section 18 T12N-R16E  
1" Iron Pipe in gravel road bed  
North 2649.50 feet to the W 1/4 Corner  
South 2666.00 feet to the W 1/4 Corner  
N45°W 41.67 feet to a nail in a 18" Ash  
N30°W 67.03 feet to a nail in a Tele Pole  
N50°E 35.76 feet to a nail in a 30" Ash  
S40°E 46.90 feet to a Stop Sign  
S30°W 68.75 feet to a nail in a 36" Ash  
S45°W 71.00 feet to a nail in a Power Pole

Signed by John A. Milletics  
Surveyor's Michigan License No. 25859

Date 11-15-1999