

JAN 19 2000

LIBER 2 PAGE 351

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>12NR</u> 16 E	<u>A-8</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

LIBER NO. 2 PAGE NO. 351  
MICHELE VANHORNAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-8 Beech 10 S20W 50; Beech 7 N54W 33  
Old Survey Liber - None  
Act 132 - None  
L.C.R.C. - None  
Unrecorded survey - Milletics Dated Aug 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-8  
W 1/4 Corner Section 19, T12N-R16E  
Found 1/2" Iron Bar in gravel Road Bed  
North 2666.00 feet to the NW Corner Section 19  
South 2664.50 feet to the SW Corner Section 19  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 8  
W 1/4 Corner Section 19 T12N-R16E  
1/2" Iron bar in gravel Road Bed with cap  
North 2666.00 feet to the NW Corner  
South 2664.50 feet to the SW Corner  
N80°W 22.90 feet to the S. End of a 12" CMP  
N60°E 39.58 feet to a nail in a 30" Ash  
S80°E 34.55 feet to a nail in a 30" Ash  
S45°E 72.49 feet to a nail in a 24" Pine

Signed by *John A. Milletics*  
Surveyor's Michigan License No. 25859

Date 11-15-1999