

JAN 19 2000

LIBER

2 PAGE 352

SECTION

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 30 AM 9:04

For corners in

LIBER NO. 2 PAGE NO. 352
NICHELE VANORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SANILAC
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 12NR 16E A-9
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-9 Hemlock 28 S31W 27; Beech 10 N34 1/2W 50
Old Survey Liber - None
L.C.R.C. - None
Act 132 - None
Unrecorded survey - Milletics Dated Jan 1985, Milletics Dated Aug 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9
SW Corner Section 19, T12N-R16E
Found 1/2" Iron bar in gravel road bed
North 2664.50 feet to the W 1/4 Corner
South 2653.08 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999
gm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 9
SW Corner Section 19 T12N-R16E
1/2" Iron Bar in Gravel Road Bed with cap
North 2664.50 feet to the W 1/4 Corner
South 2653.08 feet to the W 1/4 Corner
N45°W 67.87 feet to a nail in a Power Pole
N60°E 43.65 feet to a Stop Sign
S45°E 43.00 feet to the NW Corner of a bell riser box
S30°W 41.80 feet to a stop sign

Signed by *John A. Milletics*
Surveyor's Michigan License No. 25859

Date 11-15-1999