

JAN 19 2000

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

LIBER NO. 2 PAGE NO. 353
NICHELE VANORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

SECTION

For corners in

SANILAC
(County)

Located In:

Corner Code #

- 1. Public Land Survey T12N R 16E A-10
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-10 Sugar 6 S2W 8; Hemlock 8 N38W 14
Old Survey Liber - None
L.C.R.C. - None
Act 132 - None
Unrecorded survey - Milletics Dated Feb 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10
W 1/4 Corner Section 30, T12N-R16E
Found 1/2" Iron bar in gravel Road Bed
North 2653.08 feet to the NW Corner Section 30
South 2652.72 feet to the SW Corner Section 30
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 10
W 1/4 Corner Section 30 T12N-R16E
1/2" iron bar in gravel road bed with cap
North 2653.08 feet to the NW Corner Section 30
South 2652.72 feet to the SW Corner Section 30
N80°E 30.90 feet to a nail in a Power Pole
S80°E 30.74 feet to a nail in a Fence Post
N45°W 58.95 feet to a nail in a 6" Ash

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date 11-15-1999

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|---|----|---|---|----|---|---|----|---|----|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | | 3 | | 2 | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | | 10 | | 11 | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 19 | | | 17 | | | 16 | | | 15 | | 14 | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | | 22 | | 23 | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | | 27 | | 26 | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | | 34 | | 35 | 36 |
| 13 | | | | | | | | | | | | | |