

JAN 19 2000

LIBER

2 PAGE 354

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

99 NOV 30 AM 9:04

For corners in

SANILAC

(County)

Located In:

Corner Code #

1. Public Land Survey

T 12N R 16 E A-11

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-11 Sugar 24 S40W 48; Sugar 17 N49W 33 1/2
Old Survey Liber - None
Act 132 - Liber 2 Page 601
L.C.R.C. - None
Unrecorded survey - Sanilac Land Dated July 1979, Milletics Dated Aug 1990
Milletics Dated Feb 1997

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-11
SW Corner Section 30, T12N-R16E
Found 1" Iron Bar 6'± West of centerline in gravel road bed
North 2652.72 feet to the W 1/4 Corner
South 2637.10 feet to the W 1/4 Corner
Accepted as best evidence

APPROVED PEER BOARD MEETING
NOV 19, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 11
SW Corner Section 30 T12N-R16E
1" Iron Bar in gravel Road Bed 6'± West of centerline
North 2652.72 feet to the W 1/4 Corner
South 2637.10 feet to the W 1/4 Corner
S45°E 52.85 feet to a nail in a Power Pole
N50°E 40.00 feet to a stop sign
S50°W 31.52 feet to a stop sign
N60°W 56.00 feet to a nail in a 9" Ash

Signed by [Signature]

Date 11-15-1999

Surveyor's Michigan License No. 25859

LIBER NO. 2 PAGE NO. 354
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													