

JAN 19 2000

LIBER 2 PAGE 356

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

99 NOV 30 AM 9:04

For corners in

SANILAC

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 12N 16E A-13
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

LIBER NO. 2 PAGE NO. 356
NICHELE VANHORMAN
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on Aug. 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-13 Sugar 10 N22W 20 1/2; Cherry 9 N18E 18 1/2; Birch 10 S41E 31; Hemlock 11 S79W 30
 Old Survey Liber - None
 L.C.R.C. - None
 Act 132 - Liber 2 Page 498 Liber 2 Page 601
 Unrecorded survey - Milletics Dated March 1991, Milletics Dated Oct 1998

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
 SW Corner Section 31, T12N-R16E
 Found nothing site - State Highway Department rebuild M-46 and removed any remains of corner
 North 2657.22 feet to the W 1/4 Corner Section 31
 Reset corner from previous survey and witnesses

APPROVED PEER BOARD MEETING
 NOV 19, 1999

JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A - 13
 SW Corner Section 31 T12N-R16E
 Monu Box 1.9' feet south of existing centerline
 North 2657.22 feet to the W 1/4 Corner Section 31
 N45°E 59.90 feet to a nail in a Light Pole
 N45°W 102.60 feet to a nail in a Power Pole
 N30°W 56.90 feet to the East Leg of a Stop Sign
 S45°E 63.80 feet to the NW Corner of a Bell Riser Box
 S70°E 80.60 feet to the Road Sign

Signed by *John A. Milletics*
 Surveyor's Michigan License No. 25859

Date 11-15-1999