

JAN 22 2001

LIBER 3 PAGE 65

RECEIVED FOR RECORD

00 NOV 29 AM 11:11

LIBER NO. 3 PAGE NO. 65
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

2000 REMONUMENTATION PROGRAM

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T12N R16E	B - 13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
5. Private Claims _____

2000
John A Milletics, in a field survey on May 1, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, discovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

GLO Notes

Hemlock 16" N82 1/2°W 45 Links
Beech 5" N64°E 15 Links

Act 132 - Liber 3 Page 287

Unrecorded surveys - Milletics Oct 1998

L.C.R.C. - None

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B - 13

S 1/4 Corner Section 31 T12N-R16E

Found no evidence on site of corner State Highway removed during construction

West 2657.50 feet to the SW Corner Section 31

East 2645.50 feet to the SE Corner Section 31

Accepted as best evidence

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B - 13

S 1/4 Corner Section 31 T12N-R16E

1/2" Iron bar with cap in pavement

West 12.78 feet to the N 1/4 Corner Section 6

S10°W 52.18 feet to a Michigan Bell Riser Box

N10°W 65.18 feet to a nail in a 18" Cherry

N05°E 89.05 feet to a nail in a Power Pole

West 2657.50 feet to the SW Corner Section 31

East 2645.50 feet to the SE Corner Section 31



APPROVED PEER BOARD
MEETING Nov 25, 2000

[Signature]

signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Nov 15, 2000