

JAN 22 2001

SECTION

LIBER

3 PAGE 64

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

2000 REMONUMENTATION PROGRAM

00 NOV 29 AM 11:11

LIBER NO. 3 PAGE NO. 64
MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located in:

Corner Code #

- 1. Public Land Survey T12NR16E C - 13
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

2000

I, John A Milletics, in a field survey on May 1, ~~1998~~ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

- Hemlock 20" N49°W 45 Links
- Hemlock 18" N84°E 26 Links

Act 132 - Liber 3 Page 287 I.E. Chope Sept 1975

L.C.R.C. Forms - None

Unrecorded surveys - Milletics Oct 1998

Old Survey Liber - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 13


SE Corner Section 31 T12N-R16E

Found no evidence of corner on site, removed by State Highway Department during construction

West 2645.50 to the S 1/4 Corner Section 31

East 2652.15 to the S 1/4 Corner Section 32

Accepted as best evidence



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 13

SE Corner Section 31 T12N-R16E

1/2" Iron Bar with cap in concrete

South 3.50 feet to the centerline of M-46

S40°E 56.50 feet to a nail in a Light Pole

S45°W 68.20 feet to a nail in the top of a cut off Tele Pole

N40°E 62.12 feet to a Right of Way Marker

N40°W 63.88 feet to a cable marker sign

West 2645.50 feet to the S 1/4 Corner Section 31

East 2652.15 feet to the S 1/4 Corner Section 32

APPROVED PEER BOARD
MEETING Nov 25, 2000

[Signature]

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Nov 15, 2000