

JAN 22 2001

LIBER 3 PAGE 60

RECEIVED FOR RECORD

00 NOV 29 AM 11:11

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
2000 REMONUMENTATION PROGRAM

LIBER NO. 3 PAGE NO. 60  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SAHILAC CO., MICHIGAN

For corners in

Sanilac  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T12N R 16E      G - 13  
                                   T    R  
                                   T    R  
                                   T    R
- 2. Property Controlling    S    T    R  
    in Section                S    T    R
- 3. Miscellaneous            S    T    R  
    Property in Sec.         S    T    R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on May 1, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Notes

- Hemlock 9" N76°W 9.5 Links
- Hemlock 11" N88°E 13 Links

Act 132 - Liber 3 Page 363

Unrecorded surveys - Milletics March 1993-Milletics July 1997  
L.C.R.C. - None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 13

SE Corner Section 33 T12N-R16E

Found no evidence of corner on site, State Highway department removed corner during construction

West 2644.56 feet to the S 1/4 Corner Section 33

East 2649.60 feet to the S 1/4 Corner Section 34

Accepted as best evidence

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 13

SE Corner Section 33 T12N-R16E 1/2" Iron with cap in Concrete

North 3.02 feet to the centerline M- 46

East 30.36 feet to the NE Corner Section 4

S45°E 63.25 feet to a Stop Sign


N30°E 68.20 feet to a nail in a Power Pole

N20°W 72.98 feet to a nail in a 18" Maple

S10°E 56.70 feet to a nail in a Telephone Post

West 2644.56 feet to the S 1/4 Corner Section 33

East 2649.60 feet to the S 1/4 Corner Section 34



APPROVED PEER BOARD  
MEETING Nov 25, 2000

*jm*

Signed by John A Milletics  
Surveyor's Michigan License No. 25859

Date Nov 15, 2000