



JAN 22 2001

LIBER 3 PAGE 48

2000 Remonumentation Program

RECEIVED FOR RECORD

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

00 NOV 27 AM 8:56

For corners in

LIBER NO. 3 PAGE NO. 48
NICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T 12N R 16E	H - 7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

i. Lot No. _____, Recorded Plat _____
ii. Private Claims _____

John A. Milletics, in a field survey on May 1, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, discovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

iii. Description of original monument and accessories and/or subsequent restoration:

BLO Notes
Beech 10" N35°E 22 Links
Beech 10" S58½°E 12 Links
Act 132 - Liber 3 Page 240

iv. C.R.C. Forms - None
v. Recorded Surveys - Milletics Aug 1988, Milletics Aug 1990

vi. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1 - 7
1/4 Corner Section 15 T12N-R16E
Found 1/2" Iron Bar in Gravel Road Bed
West 2638.74 feet to the SW Corner Section 15
accepted as best evidence



vii. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1 - 7
1/4 Corner Section 15 T12N-R15E
1/2" Iron Bar in gravel road bed
North 3'± to centerline gravel, North 29.75 feet to the SW Cor of a Riser Box
N45°W 56.30 feet to a nail in a 12" Beech
N10°E 31.29 feet to a nail in a 12" Ash
S10°W 25.20 feet to a nail in a 12' Beech
West 2638.74 feet to the SW Cor. Sec. 15

APPROVED PEER BOARD
MEETING NOV 25 2000

97

Recorded by John A. Milletics Date Nov 16, 2000
Surveyor's Michigan License No. 25859