

SURVEY & REMONUMENTATION

SEP 01 1998

SECTION REMONUMENTATION

LIBER

2 PAGE 191

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 98 JUN 30 AM 10: 21
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac Located in: Corner Code #
1. Public Land Survey T13NR 12E A-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

LIBER NO. 2 PAGE NO. 191

MICHELE VANNORMAN REGISTER OF DEEDS SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, John A. Milletics, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Cell (2,6) contains a dot.

A. Description of original monument and accessories and/or subsequent restoration:

1834 GLO Notes-Harvey Parke, D.S.-Set 1/4 Sec. post-Cedar 9 N2W 22; Hemlock 6 S11W 2

Old Survey Liber F.F Rogers Act 132 By Kenneth D. Dunton

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2

Found Concrete Monument with 2" Brass Cap North 2622.31 to NW Corner Section 6 South 2639.36 to SW Corner Section 6

APPROVED PEER BOARD MEETING June 6, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2

Concrete Monument with 2" Brass Cap stamped M2 T13N-R11E N85°, 25.54'-T.C. Re-mon. tag in South face of 12" Apple Tree S08°E, 93.66'-T.C. Re-mon. tag in West face of 10" Ash S62°W, 26.84'-T.C. Re-mon. tag in Southeast face of 4" Poplar N30°W, 65.55'-T.C. Re-mon. tag in Northeast face of Power Pole



Signed by John A. Milletics Surveyor's Michigan License No. 25859

Date May 10, 1998