

SEP 01 1998

SECTION REMONUMENTATION

LIBER

2 PAGE 192

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

98 JUN 30 AM 10:21

For corners in

LIBER NO. 2 PAGE NO. 192

MICHELE VAN NORMAN REGISTER OF DEEDS SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

Table with columns: Sanilac (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

4. Lot No. , Recorded Plat
5. Private Claims

John A. Milletics, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:


1834 GLO Notes-Harvey PARKE, D.S.-Set post corner Secs. 1 & 12- Hemlock 16 N25W 31: Double Maple 12 S29W 18

Old Survey Liber F.F. Rogers Act 132 Liber 3 pages 785-786-787-788

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3 Found Concrete Monument with Brass Cap North 2639.36 Feet to W 1/4 Corner Section 6 South 2642.76 Feet to W 1/4 Corner Section 7

APPROVED PEER BOARD MEETING June 6, 1998



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3 Concrete Monument with 2" Brass Cap stamped M3 T13N-R11E N45°E, 50.18'-T.C. Re-mon. tag above found nail in Southeast face of Power Pole(+ .11192 tag in Southwest face. S75°E, 104.46'-T.C. Re-mon tag above found nail in North Face of 26" Cottonwood S60°W, 28.26'-T.C. Re-mon. tag in Southeast face of 4" Ash West, 5.0' -Survey Marker" witness post N85°W, 19.78'-T.C. Re-mon. tag in North face of 4x4 "DNR" sign post N15°W, 81.95'-T.C. Re-mon. tag in East face of Southerly trunk of double 18" cottonwood

Signed by John A. Milletics Date MAY 10, 1998 Surveyor's Michigan License No. 25859