

SEP 01 1998

SECTION REMONUMENTATION

LIBER

2 PAGE 193

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 98 JUN 30 AM 10:21
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 193

For corners in
Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T13N R12E A-4
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

MICHELE VAN NORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A. Milletics, in a field survey on May 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 GLO Notes-Harvey Parke, D.S.-Set 1/4 Sec. post-Elm 14 N48W 9; Maple 8 S54W 38

Old Survey Liber F.F. Rogers
Act 132 James A. Beck
Act 132 Liber 3 Page 785-786-787-788

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4
Found Concrete Monument with Brass Cap
North 2642.76 To NW Corner Section 7
South 2642.41 To SW Corner Section 7

APPROVED PEER BOARD MEETING
June 6, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4

Concrete Monument with 2" Brass Cap stamped M4 T13N-R11E
N65°E, 36.02'-T.C. Re-mon. tag above found nail in Northwest face of 16" Ash
S80°E, 33.00'-Found 1/2" Iron rod with #11192
S20°W, 41.13'-T.C. Re-mon. tag above found nail in East face of 16" Ash
N80°W, 30.07'-T.C. Re-mon. tag above found nail in South face of 10" dead Poplar
N78°W, 22.99'-T.C. Re-mon. tag in the Northeast face of 8" Ash

Signed by John A. Milletics Date May 10, 1998

Surveyor's Michigan License No. 25859

