

REMONUMENTATION

SEP 01 1998

SECTION REMONUMENTATION

LIBER

2 PAGE 195

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE 98 JUN 30 AM 10:21

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER NO. 2 PAGE NO. 195

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T 13NR 12E	A-6
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

MICHELE VAN NORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1834 GLO Notes-Harvey Parke, D.S.-Set 1/4 Sec. post-Beech 8 S7W; Beech 10 N20W 39

Old Survey Liber F.F. Rogers
Act 132 Liber 3 Pages 322-323

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6
Found Concrete Monument with Brass Cap
North 2634.97 NW Corner Section 18
South 2649.28 SW Corner Section 18

APPROVED PEER BOARD MEETING
June 6 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6

Concrete Monument with 2" Brass Cap stamped M6 T13N-R11E
N42°E, 43.59' Re-mon. tag in Southeast face of 10" Cedar
N65°E, 170.0'-Southeast corner of Brick house
S35°E, 47.32'-T.C. Re-mon. tag in Southwest face of 5" Spruce
S42°W, 26.69'-Set 1/2" Diameter reinforcing rod
N15°W, 78.43'-T.C. Re-mon. tag in West face of 9" forked Black Walnut Tree:

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date May 10, 1998

