

SURVEY & REMONUMENTATION

MAY 07 1997 LIBER

2 PAGE 104

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 104
ESTHER LEE
REGISTER OF DEEDS
SAMILAC CO., MICHIGAN

For corners in **COMMISSION**

Sanilac Located in: Corner Code #
(County)

1. Public Land Survey T13N R12E (A-13) B-13
T R
T R
T R
T R

2. Property Controlling S T R
In Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Aug 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
A-13 GLO Notes No Old Survey Liber
Set Post Act 47 Tuscola Co. Act 132 Liber 3 Page 110
Hemlock 24 S64W 20
Hemlock 10 N23½E 5

B-13 GLO Notes No Old Survey Liber
40.00 Set 1/4 Section Post Act 74 None, Act 132 Liber 3 Page 110
Willow 14 N80E 2.42
Birch 10 N86W 2.47

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 SW Corner Section 31 T13N-R12E
Found Conc Monu in place with Cap

B-13 S 1/4 Cor Section 31 T13N-R12E
Found 1/2" Iron Bar in road trail

APPROVED PEER BOARD MEETING
12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 SW Corner Section 31 T13N-R12E
Conc Monu With Cap
S45°W 41.20 to a nail in a Fence Post
N85°W 29.80 to a nail in a Riser Post
N45°E 51.00 to a nail in a 18" Poplar
N80°E 63.80 to a nail in a 18" Ash
East 2103.10 to the S 1/4 Cor

B-13 S 1/4 Cor Section 31 T13N-R12E
1/2" Iron Bar in trail road
East 35.55 to a 1/2" Iron Bar
S70°E 11.00 to a nail in a 18" Cottonwood
N60°W 38.60 to a nail in a 18" Cottonwood
S45°W 4.60 to a nail in a 18" Cottonwood
West 2103.10 to the SW Cor
East 2619.86 to the SE Cor

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

