

MAY 07 1997 LIBER

2 PAGE 104

REMONUMENTATION

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 104
ESTHER LEE
REGISTER OF DEEDS
SAMILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13NR12E	A-13 B-13
	T___R___	_____
	T___R___	_____
	T___R___	_____
2. Property Controlling in Section	S___T___R___	_____
	S___T___R___	_____
3. Miscellaneous Property in Sec.	S___T___R___	_____
	S___T___R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Millettics, in a field survey on Aug 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-13 GLO Notes No Old Survey Liber
Set Post Act 47 Tuscola Co. Act 132 Liber 3 Page 110
Hemlock 24 S64W 20
Hemlock 10 N23½E 5

B-13 GLO Notes No Old Survey Liber
40.00 Set 1/4 Section Post Act 74 None, Act 132 Liber 3 Page 110
Willow 14 N80E 2.42
Birch 10 N86W 2.47

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
SW Corner Section 31 T13N-R12E
Found Conc Monu in place with Cap
B-13
S 1/4 Cor Section 31 T13N-R12E
Found 1/2" Iron Bar in road trail

APPROVED PEER BOARD MEETING

12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 SW Corner Section 31 T13N-R12E	B-13 S 1/4 Cor Section 31 T13N-R12E
Conc Monu With Cap	1/2" Iron Bar in trail road
S45°W 41.20 to a nail in a Fence Post	East 35.55 to a 1/2" Iron Bar
N85°W 29.80 to a nail in a Riser Post	S70°E 11.00 to a nail in a 18" Cottonwood
N45°E 51.00 to a nail in a 18" Poplar	N60°W 38.60 to a nail in a 18" Cottonwood
N80°E 63.80 to a nail in a 18" Ash	S45°W 4.60 to a nail in a 18" Cottonwood
East 2103.10 to the S 1/4 Cor	West 2103.10 to the SW Cor
	East 2619.86 to the SE Cor

Signed by John A Millettics
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

