

Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

95 JUL 10 AM 9:27

LIBER NO. 2 PAGE NO. 57  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located In:

Corner Code =#

- 1. Public Land Survey T 13N R 12E C-7
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Milletics, in a field survey on May 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C - 7 GLO Notes

Set Post at 80 Chains Hemloch 13 N40E 13, Hemloch 11 S18E 35

Old Survey Liber Page 140 April 1895, Act 74 Form None Act 132 Form Liber 3 Page 657

State Highway Book Page 10

Approved Peer Group Meeting May 25, 1995

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C - 7

SE Cor Section 18 T13N-R12E

Found Monu Box

N50°E 59.25 to a nail in a Power Pole

N50°W 62.70 to a R/W Marker

S60°W 54.85 to a Stop Sign

S40°W 109.02 to the NE Cor of a Block Building

West 6.4 to centerline of pavement

REMONUMENTATION SURVEY & REMONUMENTATION

JUL 3 1995

JUL 3 1 1995

COMMISSION

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-7

SE Cor Section 18 T13N-R12E

Found Monu Box

N50°E 59.25 to a nail in a Power Pole

N50°W 62.70 to a R/W Marker

S60°W 54.85 to a Stop Sign

S40°W 109.02 to the NE Cor of a Block Building

West 6.4' to the center line of pavement



Signed by John A. Milletics

Date May 22, 1995

Surveyor's Michigan License No. 25859