

REMONUM

MAY 17 1997 LIBER

2 PAGE 105

COMMISSION

REMONUMENTION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 105
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T 13NR 12E	C-13 D-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	P
1													
2	6		5		4			3		2			1
3													
4	7		8		9			10		11			12
5													
6	18		17		16			15		14			13
7													
8	19		20		21			22		23			24
9													
10	30		29		28			27		26			25
11													
12	31		32		33			34		35			36
13													

I, John A Milletics, in a field survey on Aug 3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
C-13 GLO Notes No Old Survey Liber
80.00 Set Post Corner Act 74 None, Act 132 Liber 3, Page 110
B. Ash 20 N72½E 15 State Highway Right of Way Book Page 8
B. Ash 12 N47W 40 Unrecorded survey dated 5-23-96

D-13 GLO Notes No Old Survey Liber
40.00 Set 1/4 Section Post Act 74 None, Act 132 None
Hemlock 11 N67½W 25 Unrecorded survey dated 5-23-96
Hemlock 11 N44E 18

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13
SE Corner Section 31 T13N-R12E
Found Monu Box

D-13
S 1/4 Corner Section 32 T13N-R12E
Found 1/2" Iron Bar in a 1" Pipe

APPROVED PEER BOARD MEETING
12-02-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
C-13 SE Corner Section 31 T13N-R12E
Monu Box in M-53
N50°W 59.00 to a nail in a Tale Pole
S45°E 73.00 to a nail in a Power Pole
N50°E 81.85 to a nail in a Tele Pole
S50°E 53.00 to a Project Marker
West 2619.86 to the S 1/4 Cor
East 2610.24 to the S 1/4 Cor
D-13 S 1/4 Corner Section 32 T13N-R12E
1/2" Iron Bar in a 1" Pipe
West 13.53 to a 1/2" Iron Bar
S40°E 70.25 to a nail in a Power Pole
S15°W 29.30 to a nail in a Fence Post
N15°E 25.00 to a nail in a 18" Ash
N20°E 23.00 to a Bell Box
West 2610.24 to the SW Cor
East 2628.58 to the SE Cor

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

