

**SURVEYOR'S  
REMONUMENTATION**

MAY 07 1997 LIBER

2 PAGE 105

RECEIVED FOR RECORD

COMMISSION

REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 105

ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located in:

Corner Code #

1. Public Land Survey

T 13N R 12E

C-13, D-13

T R

T R

T R

2. Property Controlling  
in Section

S T R

3. Miscellaneous  
Property in Sec.

S T R

S T R

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, John A. Milletics, in a field survey on Aug 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-13 GLO Notes

80.00 Set Post Corner

B. Ash 20 N72½E 15

B. Ash 12 N47W 40

No Old Survey Liber

Act 74 None, Act 132 Liber 3, Page 110

State Highway Right of Way Book Page 8

Unrecorded survey dated 5-23-96

D-13 GLO Notes

40.00 Set 1/4 Section Post

Hemlock 11 N67½W 25

Hemlock 11 N44E 18

No Old Survey Liber

Act 74 None, Act 132 None

Unrecorded survey dated 5-23-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13

SE Corner Section 31 T13N-R12E

Found Monu Box

D-13

S 1/4 Corner Section 32 T13N-R12E

Found 1/2" Iron Bar in a 1" Pipe

APPROVED PEER BOARD MEETING

12-22-96 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13 SE Corner Section 31 T13N-R12E

Monu Box in M-53

N50°W 59.00 to a nail in a Tele Pole

S45°E 73.00 to a nail in a Power Pole

N50°E 81.85 to a nail in a Tele Pole

S50°E 53.00 to a Project Marker

West 2619.86 to the S 1/4 Cor

East 2610.24 to the S 1/4 Cor

D-13 S 1/4 Corner Section 32 T13N-R12E

1/2" Iron Bar in a 1" Pipe

West 13.53 to a 1/2" Iron Bar

S40°E 70.25 to a nail in a Power Pole

S15°W 29.30 to a nail in a Fence Post

N15°E 25.00 to a nail in a 18" Ash

N20°E 23.00 to a Bell Box

West 2610.24 to the SW Cor

East 2628.58 to the SE Cor

Signed by [Signature]

Surveyor's Michigan License No. 25859

Date Nov 15, 1996

