

REMONUMENTATION

LIBER COMMISSION

2 PAGE 106

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD 96 DEC 10 AM 11:56 LIBER NO. 2 PAGE NO. 106 ESTHER LEE REGISTER OF DEEDS SANILAC CO. MICHIGAN

For corners in

Table with columns: Sanilac (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, John A Milletics, in a field survey on Aug 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. Contains numbers 1-36 in a grid pattern.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: E-13 GLO Notes, 80.00 Set Post Corner, B. Ash 14 N62W 23, Birch 7 N80E 6; F-13 GLO Notes, 40.00 Set 1/4 Section Post, Beech 12 N53E 34, Beech 10 N39 1/2 W 32

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: E-13 SW Corner Section 33 T13N-R12E Found 1/2" Iron Bar in Gravel Road Bed; F-13 S 1/4 Cor Section 33 T13N-R12E Found 1/2" Smooth Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING 12-02-96 JM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: E-13 SW Corner Section 33 T13N-R12E 1/2" Iron Bar in gravel Road Bed West 9.85 feet to a 1/2" Iron Bar S45°W 52.55 to a nail in a Power Pole N45°W 50.15 to a nail in a Tele Riser West 2628.58 to the S 1/4 Cor East to the S 1/4 Cor; F-13 S 1/4 Corner Section 33 T13N-R12E 1/2" Smooth Iron Bar in Gravel Road Bed West 22.30 to a T Bar S50°W 31.60 to a nail in a Fence Post N10°W 54.70 to a nail in a 6" Oak West to the SW Cor East to the SE Cor

Signed by [Signature] Surveyor's Michigan License No. 25859

Date Nov 15, 1996

