

REMONUMENTATION

MAY 07 1997 LIBER

2 PAGE 109

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 109  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T13N R12E	G-13 H-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on Aug 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

G-13 GLO Notes  
80.00 Set Post Corner  
Cedar 7 N72W 19  
Tamarack 16 N27E 20  
No Old Survey Liber  
Act 74 None, Act 132 Liber 3 Page 247

H-13 GLO Notes  
40.00 Set 1/4 Section Post  
Hemlock 18 N37W 16  
Hemlock 8 N79E 35  
No Old Survey Liber  
Act 74 None Act 132 Liber 3 Page 247

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13  
SW Corner Section 34 T13N-R12E  
Found 3/4" Iron Bar

H-13  
S 1/4 Cor Section 34 T13N-R12E  
Found 2" Iron Bar

APPROVED PEER BOARD MEETING  
12-02-96 JAM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 SW Corner Section 34 T13N-R12E	H-13 S 1/4 Corner Section 34 T13N-R12E
3/4" Iron Bar in gravel	2" Iron Bar in gravel Road Bed
West 36.30 to a 3/4" Iron Bar	N05°W 28.60 to a Tele Post Box
West 19.90 to pavement Centerline	N45°E 25.00 to a nail in a 12" Oak
N40°E 70.70 to a nail in a Anchor Pole	N60°E 40.30 to a nail in a 10" Pine
N45°W 80.80 to a nail in a Power Pole	West 2629.08 to the SW Cor
S50°W 65.70 to a nail in a Anchor Pole	East 2629.08 to the SE Cor
West 2620.90 to S 1/4 Cor	
East 2629.08 to S 1/4 Cor	

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date Nov 15, 1996  
John A. Milletics  
Land Surveyor  
No. 25859