

MAY 07 1997 LIBER

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

COMMISSION

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 109 ESTHER LEE REGISTER OF DEEDS SANILAC CO. MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R12E	G-13 H-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat 5. Private Claims

I, John A. Milletics, in a field survey on Aug 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														
2	6			5			4			3			2	1
3														
4	7			8			9			10			11	12
5														
6	10			17			16			15			14	13
7														
8	19			20			21			22			23	24
9														
10	30			29			28			27			26	25
11														
12	31			32			33			34			35	36
13														

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-13 GLO Notes: 80.00 Set Post Corner Cedar 7 N72W 19 Tamarack 16 N27E 20 No Old Survey Liber Act 74 None, Act 132 Liber 3 Page 247
- H-13 GLO Notes: 40.00 Set 1/4 Section Post Hemlock 18 N37W 16 Hemlock 8 N79E 35 No Old Survey Liber Act 74 None Act 132 Liber 3 Page 247

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-13: SW Corner Section 34 T13N-R12E Found 3/4" Iron Bar
- H-13: S 1/4 Cor Section 34 T13N-R12E Found 2" Iron Bar

APPROVED PEER BOARD MEETING 12-02-96 JAM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-13 SW Corner Section 34 T13N-R12E: 3/4" Iron Bar in gravel West 36.30 to a 3/4" Iron Bar West 19.90 to pavement Centerline N40°E 70.70 to a nail in a Anchor Pole N45°W 80.80 to a nail in a Power Pole S50°W 65.70 to a nail in a Anchor Pole West 2620.90 to S 1/4 Cor East 2629.08 to S 1/4 Cor
- H-13 S 1/4 Corner Section 34 T13N-R12E: 2" Iron Bar in gravel Road Bed N05°W 28.60 to a Tele Post Box N45°E 25.00 to a nail in a 12" Oak N60°E 40.30 to a nail in a 10" Pine West 2629.08 to the SW Cor East 2629.08 to the SE Cor

Signed by [Signature] Surveyor's Michigan License No. 25859

Date Nov 15, 1996 John A. Milletics Land Surveyor No. 25059