

HEMONI

RECEIVED FOR RECORD

MAY 17 1987

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 11:56

COMMISSION
For corners in

LIBER NO. 2 PAGE NO. 108

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R12E	I-13 J-13
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A. Milletics, in a field survey on Aug 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- I-13 GLO Notes No Old Survey Liber
80.00 Set Section Post Corner Act 74 None, Act 132 None
Birch 12 N42E 11
Hemlock 26 N57½W 16
 - J-13 GLO Notes No Old Survey Liber
40.00 Set 1/4 Section Post Act 74 None, Act 132 None
Aspen 15 N86½W 24
Hemlock 9 N61E 23½

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- I-13 SE Corner Section 34 T13N-R12E
Found 1" Iron Bar Set by I.E. Chope note during Survey
recorded Liber 3 Page 247
 - J-13 Set 1/2" Iron Bar in gravel Road Bed at equal distance
between SE and SW Cor of Section. Found no evidence of corner.
no fences in the mile.

APPROVED PEER BOARD MEETING
12-02-96 JM

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- I-13 SE Corner Section 34 T13N-R12E
1" Iron bar in gravel road bed
West 68.64 to a 3/4" Iron Bar
N50°E 56.30 to a nail in a Tele Pole
South 21.00 to the West leg of a Road Sign
S10°W 110.40 to a nail in a Tele Pole
West 2629.08 feet to the S 1/4 Corner
East 2632.04 feet to the S 1/4 Corner
 - J-13 S 1/4 Corner Section 35 T13N-R12E
1/2" Iron Bar
West 61.08 to a 1/2" Iron Bar
S75°W 34.65 to a nail in a 24" Cottonwood
S80°W 49.05 to a nail in a 24" Cottonwood
S15°W 27.80 to a nail in a 8" Pine
S05°E 25.05 to a metal Fence Post

Signed by [Signature]
Surveyor's Michigan License No. 25859

Date Nov 15, 1996

