

MAY 07 1997

REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 DEC 10 AM 11:56

LIBER NO. 2 PAGE NO. 108 ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

COMMISSION For corners in

Table with columns: Sanilac (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat 5. Private Claims

I, John A Milletics, in a field survey on Aug 10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

I-13 GLO Notes 80.00 Set Section Post Corner Birch 12 N42E 11 Hemlock 26 N57 1/2 W 16 No Old Survey Liber Act 74 None, Act 132 None

J-13 GLO Notes 40.00 Set 1/4 Section Post Aspen 15 N86 1/2 W 24 Hemlock 9 N61E 23 1/2 No Old Survey Liber Act 74 None, Act 132 None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 SE Corner Section 34 T13N-R12E Found 1" Iron Bar Set by I.E. Choep note during Survey recorded Liber 3 Page 247

J-13 Set 1/2" Iron Bar in gravel Road Bed at equal distance between SE and SW Cor of Section. Found no evidence of corner, no fences in the mile.

APPROVED PEER BOARD MEETING

12-02-96 97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13 SE Corner Section 34 T13N-R12E 1" Iron bar in gravel road bed West 68.64 to a 3/4" Iron Bar N50°E 56.30 to a nail in a Tele Pole South 21.00 to the West leg of a Road Sign S10°W 110.40 to a nail in a Tele Pole West 2629.08 feet to the S 1/4 Corner East 2632.04 feet to the S 1/4 Corner J-13 S 1/4 Corner Section 35 T13N-R12E 1/2" Iron Bar West 61.08 to a 1/2" Iron Bar S75°W 34.65 to a nail in a 24" Cottonwood S80°W 49.05 to a nail in a 24" Cottonwood S15°W 27.80 to a nail in a 8" Pine S05°E 25.05 to a metal Fence Post

Signed by [Signature] Surveyor's Michigan License No. 25859

Date Nov 15, 1996

