

REMONUMENTATION

LIBER

2 PAGE 107

RECEIVED FOR RECORD

MAY 07 1997

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 10 AM 11:56

COMMISSION

LIBER NO. 2 PAGE NO. 107

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R12E	K-13 L-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on Aug 17, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-13 GLO Notes

80.00 Set Post Corner
Hemlock 10 N55E 10
Pine 11 N69W 33½

No Old Survey Liber

No Act 74, No Act 132

Road Comm Notes showing corner no witnesses

L-13 GLO Notes

40.00 Set 1/4 Section Post
Pine 36 N45W 6
B Ash 10 N87E 23

No Old Survey Liber

No Act 74, No Act 132

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13

SW Corner Section 36 T13N-R12E
Set 1/2" Iron Bar GLO Distance From NW of Section 1
Proportions with existing fences

APPROVED PEER BOARD MEETING

12-02-96-97

L-13

S 1/4 Corner Section 36 T13N-R12E
Set 1/2" Iron bar at equal distance between SE and SW Corners of Section

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 SW Corner Section 36 T13N-R12E

1/2" Iron Bar
West 38.94 feet to a 1/2" Iron Bar
S60°W 66.10 to a nail in a 10" Pine
N80°W 85.60 to a nail in a Tele Pole
West 7.90' to the Centerline of Germania Road
S20°E 114.45 to a nail in a Power Pole
West 2632.04 to the S 1/4 Corner
East 2626.18 to the S 1/4 Corner

L-13 S 1/4 Corner Section 36 T13N-R12E

1/2" Iron Bar
S45°W 21.80 to a nail in a 10" Ash
N45°W 27.70 to the East End of a 18" CMP
N10°E 62.25 to a nail in a Power Pole
N05°W 95.40 to a nail in a 10" Ash
West 2626.18 to the SW Corner
East 2626.18 to the SE Corner

Signed by _____ Date Nov 15, 1996

Surveyor's Michigan License No. 25859

