

APR 14 1998

LIBER 2 PAGE 156

SECTION

1997 REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in EVERGREEN TOWNSHIP

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>13N</u> R <u>12E</u>	<u>K5</u>
	T <u>13N</u> R <u>12E</u>	<u>L5</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

RECEIVED FOR RECORD  
97 DEC -2 AM 9:09  
LIBER NO. 12 PAGE NO. 156  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

SURVEY & REMONUMENTATION  
JAN 08 1998

SECTION  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Millettics, in a field survey on Oct. 26, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.


1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

L5	G.L.O. Notes Set quarter Section Post Beech 30 S16W 10, Hemlock 6 N10W 11, and 14 Act 74 Form - None Act 132 Form - None Road Commission Record - None Drain Commission Record - None	K5	G.L.O. Notes Set Post Corner Sections 11, 12, 13, Hemlock 36 S85E 24, Hemlock 5 S56W 7 Act 74 Form - None Act 132 Form - None Road Commission Record - None Drain Commission Record - None
----	--	----	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L5	Found 3/4" Re-Rod in Monument Box	K5	Found 5/8" Re-Rod in Monument Box
----	-----------------------------------	----	-----------------------------------



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L5 1/4 Corner Sections 12 and 13, T13N-R12E Found 3/4" Re-Rod in Monument Box WITNESSES: N45°E 29.85' to 1/2" Steel Stake S45°E 32.75' to 1/2" Steel Stake S45°W 25.10' to 1/2" Steel Stake N45°W 30.02' to 1/2" Steel Stake East 2705.20' to M5, T13N-R12E West 2703.95' to K5, T13N-R12E	K5 Corner Sections 11, 12, 13, and 14, T13N-R12E Found 5/8" Re-Rod in Monument Box WITNESSES: N45°E 52.0' to 1/2" Steel Stake S40°E 87.53' to Spike S.W. Side Corner Post S45°W 77.70' to Lag Bolt E. Side P.P. N45°W 69.55' to Spike S.W. Cor. 4"x4" Wood Post East 2703.95' to L5, T13N-R12E West 2630.83' to Apparent J5, T13N-R12E
--	--

Signed by John A. Millettics  
Surveyor's Michigan License No. 25859

Date Nov 12, 1997

PEER GROUP APPROVED  
AT MEETING HELD

NOV. 26 97, 1997