

SEP 01 1998

LIBER

2 PAGE 202

RECEIVED FOR RECORD

SECTION REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

98 JUN 30 AM 10:21

LIBER NO. 2 PAGE NO. 202

For corners in Sanilac

(County)

Located In:

Corner Code #

1. Public Land Survey

T 13NR12E

A-13

Reg. # 2

T 12NR11E

M-1 (Tuscola)

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

MICHELE VANNORMAN
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

John A. Milletics, in a field survey on May 1, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 10 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

1834- GLO Notes-Harvey Parke, D.S.-Township Corner est.-Hemlock 24 S64W 20; Hemlock 10 N23 1/2E 5

Old survey Liber Dated 1889 F.F. Rogers
Act 132 Liber 3 Pages 116 & 117

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13
Found Concrete Monument with Brass Cap
North 2638.80 to the W 1/4 Corner Section 31

APPROVED PEER BOARD MEETING
June 16, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13

Concrete Monument with 2" Brass Cap stamped M1 T12N-R11E (Set September 20, 1994.)
N54°E, 51.41' -T.C. Re-mon. tag set in Northwest face of 14" Poplar(found nail-Flagging SW fac
S68°E, 84.69'-T.C. Re-mon. tag set in Southwest face of 8" Basswood
S42°E, 41.05'-T.C. Re-mon. tag set in West leg of upright Steel Vehicle Frame
N75°W, 29.78' -T.C. Re-mon. tag set above found nail in South face of telephone pedstal suppor

NOTE: This corner is common with: M-1, T12N-R11E.

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date May 10, 1998

