

LIBER

2 PAGE 244

RECEIVED FOR RECORD

98 DEC -1 AM 9:09

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 244

MICHELE VAN NORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R13E	A-12
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Milletics, in a field survey on Oct 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-12 GLO Notes - Hemlock 13 S33W 38; Cedar 18 N49W 34 SURVEY & REMONUMENTATION  
 Old Survey Liber - None  
 Act 132 - None  
 L.C.R.C. - None  
 Unrecorded Surveys Dated 8-30-78  
 9-27-96  
 9-23-98

JAN 15 1999

SECTION



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12 W 1/4 Corner Section 31 T13N-R13E  
 Found 1/2" Iron Bar in Gravel Road Bed at halfway distance between the NW and SW corners on line.  
 Accepted as best evidence

North 2653.96 feet to the NW Corner Section 31  
 South 2653.96 feet to the SW Corner Section 31

APPROVED PEER BOARD MEETING  
 NOV 30, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12

1/2" Iron Bar with cap  
 East, 57.0' To Nail in 18" Ash  
 N45°W 25.00 to a 1/2" Iron Bar  
 S45°W 25.00 to a 1/2" Iron Bar

North 2653.96 feet to the NW Corner Section 31  
 South 2653.96 feet to the SW Corner Section 31

Signed by John A. Milletics  
 Surveyor's Michigan License No. 25859

Date Nov 18, 1998