

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 MAY 15 AM 8:18

LIBER NO. 2 PAGE NO. 83
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R13E	A-13, B-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Millettias, in a field survey on March 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A - 13 GLO Notes
80.21 Intersected Line Set Post NO survey in Old Liber
Hemlock 24" S64W 20 Links Unrecorded survey dated 1030, 78 Sanilac Land
Hemlock 10" n23½E 5 Links Act 74 None Act 132 None
- B - 13 GLO Notes
Set 1/4 Post at 40 Chains NO survey in Old Liber
Willow 14" N80E 2.42 Unrecorded survey dated 10,30,78 Sanilac Land
Birch 10" N86W 2.47 Act 74 None Act 132 None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A - 13
SW Cor Section 31 T13N-R13E
Found 1" Square Bar
- B - 13
S 1/4 Cor Section 31 T13N-R13E
Found 1/2" Iron Bar

APPROVED PEER BOARD MEETING
APRIL 30, 1996 *JM*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- A - 13
SW Cor Section 31 T13N-R13E
1" Square Iron Bar in Gravel Road Bed
N45W 32.90 to the center of a USGS Marker
N70E 37.00 to a nail in a 30" Cottonwood
S45E 38.00 to a nail in a 24" Maple
S25E 62.50 to a nail in a 18" Maple
East 2673.44 to S 1/4 Corner
- B - 13
S 1/4 Cor Section 31 T13N-R13E
1/2" Iron Bar in Gravel Road Bed
South 4'± to centerline of Gravel Road
North 77.00 to a nail in a 24" Poplar
N50W 53.10 to a Tele Riser Box
N60E 48.60 to a nail in a 12" Poplar
West 2673.44 to SW Corner
East 2659.48 to SE Corner

State of Michigan
Signed by John A. Millettias
Surveyor's Michigan License No. 25859
Land Surveyor
No. 25859

Date April 9, 1996