

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

96 MAY 15 AM 8:18

For corners in

Sanilac  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T13N R 13E      C - 13, D - 13
- T      R
- T      R
- T      R
- 2. Property Controlling    S      T      R
- in Section                S      T      R
- 3. Miscellaneous            S      T      R
- Property in Sec.         S      T      R

LIBER NO. 2 PAGE NO. 84  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on March 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- C - 13 GLO Notes  
Set Post at 80 Chains      NO Survey in Old Liber  
B. Ash 20" N72½E 15 Links      NO Act 132 NO Act 74  
B. Ash 12" N47W 40 Links      Road Comm Monu Box

- D - 13 GLO Notes  
Set Post 40 Chains      NO Survey in Old Liber  
Hemlock 11" N67½W 25 Links      NO Act 132 NO Act 74  
Hemlock 11" N44W 18 Links      Unrecorded survey I.E. Chope

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C - 13  
SW Cor Section 32 T13N-R13E  
Found Monu Box
- D - 13  
S 1/4 Cor Section 32  
Found R/R Spike in Gravel Road Bed

APPROVED PEER BOARD MEETING  
APRIL 30, 1996 *JM*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                                      |   |
|--------------------------------------|---|
| C - 13                               | D - 13                                      |
| SW Cor Section 32 T13N-R13E          | S 1/4 Cor Section 32 T13N-R13E              |
| Monu Box                             | 1" Iron Bar                                 |
| West 16.67 to a Monu Box             | North 207.17 feet to a nail in a Power Pole |
| N40E 62.60 to SW Cor of a Bell Box   | N05E 56.80 feet to a nail in a 6" Poplar    |
| N45W 83.15 to a nail in a Power Pole | N07E 32.80 feet to a nail in a 6" Poplar    |
| East 2641.74 feet to the S 1/4 Cor   | West 2641.74 feet to the SW Cor             |
| West 2659.48 feet to the S 1/4 Cor   | East 2641.74 feet to the SE Cor             |



Date April 9, 1996