

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 MAY 15 AM 8:18

For corners in

Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T13N R13E E-13, F-13
T R
T R
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

LIBER NO. 2 PAGE NO. 85
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A Milletics, in a field survey on March 15, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- E - 13 GLO Notes NO Old Survey Liber
Set Post 80.00 Chains Unrecorded I.E. Chope Survey
B. Ash 14" N62W 23 Links Unrecorded Survey dated 12,22,81 Northwestern Survey
Birch 7" N80E 6 Links NO Act 74 , NO Act 132
- F - 13 GLO Notes NO Old Survey Liber
Set Post 40.00 Chains NO Act 132
Beech 12" N53E 34 Links NO Act. 74
Beech 10" N39 1/2 W 32 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E - 13 SW Cor Section 33 T13N-R13E
Found 1" Iron Bar in Gravel Road Bed
- F - 13 S 1/4 Cor Section 33 T13N-R13E
Found 1/2" Iron Bar in Gravel Road Bed

APPROVED PEER BOARD MEETING
APRIL 30, 1996 JM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E - 13 SW Cor Section 33 T13N-R13E
1" Iron Bar
N70E 186.38 to a nail in a Power Pole
N60W 181.03 to a nail in a Power Pole
N30W 39.50 to a stop sign
S30E 35.60 to a stop sign
East 2643.60 feet to S 1/4 Cor
West 2641.74 feet to S 1/4 Cor
- F - 13 S 1/4 Cor Section 33 T13N-R13E
1 1/2" Iron Bar
North 53.50 to a nail in a Power Pole
N45W 54.35 to a nail in a 30" Maple
N70W 106.35 to a nail in a 30" Maple
East 2643.60 feet to the SE Cor
West 2643.60 feet to the SW Cor

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date April 9, 1996

