

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 MAY 15 AM 8:18

LIBER NO. 2 PAGE NO. 86
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located in:	Corner Code #
1. Public Land Survey	T13N R13E	G-13, H-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on March 15, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G - 13 GLO Notes NO Old Survey Liber
Set Post at 80 Chains NO Act 132 NO Act 74
Cedar 7" N72W 19 Links State Highway Book Page 25
Tamarack 16" N27E 20 Links

H - 13 GLO Notes NO Old Survey Liber
Set Post at 40 Chains NO Act 132 NO Act 74
Hemlock 18" N37W 16 Links Unrecorded Survey dated 9-6-95
Hemlock 8" N79E 35 Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G - 13 SW Cor Section 34 T13N-R13E
Found Monument Box in Place
H - 13 S 1/4 Cor Section 34 T13N-R13E
Found 1/2 Iron Bar in gravel Road Bed

APPROVED PEER BOARD MEETING
APRIL 30, 1996 97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 13 SW Cor Section 34 T13N-R13E
MONUMENT BOX in Centerline of pavement
S45E 42.15 to a nail in a Tele Pole
N45W 74.00 to a nail in a Power Pole
N70W 73.55 to a nail in a Power Pole
West 2643.60 feet to the S 1/4 Cor
East 2649.96 feet to the S 1/4 Cor
H - 13 S 1/4 Cor Section 34 T13N-R13E
1/2" Iron Bar in Gravel Road
North 57.30 to a nail in a Power Pole
S05W 116.00 to the NE Cor of a House
S30W 40.55 to a nail in a 18" Ash
S50W 60.55 to a nail in a 30" Maple
East 2663.92 feet to the SE Cor
West 2649.96 feet to the SW Cor

Date April 9, 1996



Signed by John A. Milletics
Surveyor's Michigan License No. 25859