

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 MAY 15 AM 8:18

LIBER NO. 2 PAGE NO. 87
ESTHER LEE
REGISTER OF DEEDS
SANB AG CO. MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T13N R13E	I-13, J-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on March 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- I - 13 GLO Notes NO Old Survey Liber
Set Post 80.00 Chains NO Act 74
Birch 12" N42E 11 Links NO Act 132 - Unrecorded Survey dated 9-6-95
Hemlock 26" N57½W 16 Links
 - J - 13 GLO Notes NO Old Survey Liber
Set Post at 40 Chains NO Act 74
Aspen 15" N86½W 24 Links Act 132 Liber 3 Page 670
Hemlock 9" N61E 23½ Links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I - 13 SW Cor Section 35 T13N-R13E
Found 1/2" Iron Bar in gravel road bed
- J - 13 S 1/4 Cor Section 35 T13N-R13E
Found 1/2" Iron Bar in gravel road bed.

APPROVED PEER BOARD MEETING
APRIL 30, 1996 *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I - 13 SW Cor Section 35 T13N-R13E
1/2" iron bar in gravel road bed
S05W 48.75 to a nail in a Power Pole
N45E 48.10 to a nail in a Power Pole
S50W 75.10 to a nail in a Power Pole
N45W 43.50 to a stop sign
West 2663.92 feet to S 1/4 Cor
East 2645.33 feet to S 1/4 Cor
- J - 13 S 1/4 Cor Section 35 T13N-R13E
1/2" iron bar in gravel road bed
West 29.75 to 1" Iron bar in road bed
N30E 41.70 to a nail in a tele pole
North 15.8 to a metal fence post
N50W 38.00 to a metal fence post
S60W 60.40 to a nail in a fence post
East 2645.33 to SE Cor
West 2645.33 to SW Cor

Signed by John A. Milletics
Surveyor's Michigan License No. 25859
Land Surveyor
No. 25859

Date April 10, 1996