

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

96 MAY 15 AM 8:18

LIBER NO. 2 PAGE NO. 88
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in

Sanilac

(County)

Located in:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----|---|-----|--------------|
| 1. Public Land Survey | T | 13N | R | 13E | (K-13), L-13 |
| | T | | R | | |
| | T | | R | | |
| | T | | R | | |
| 2. Property Controlling in Section | S | | T | R | |
| | S | | T | R | |
| 3. Miscellaneous Property in Sec. | S | | T | R | |
| | S | | T | R | |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, John A. Milletics, in a field survey on March 18, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- K - 13 GLO Notes Act 132 Liber 3 Page 670
Set Post 80.00 Chains Act 74 None
Hemlock 10" N55E 10 Links Old Survey Liber None
Pine 11" N69W 33½ Links
- L - 13 GLO Notes Act 74 None
Set Post 40 Chains Unrecorded Survey dated 11-5-91
Aspen 15" N86½W 24 Links Act 132 None
Hemlock 9" n61E 23½ Links Old Survey Liber None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K - 13
SW Cor Section 36 T13N-R13E
Found 1" Iron Bar in gravel Road Bed
- L - 13
S 1/4 Cor Section 36 T13N-R13E
Found 5/8" Iron bar in gravel road bed

APPROVED PEER BOARD MEETING
APRIL 30, 1996 *EM*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| K-13
SW Cor Section 36 T13N-R13E
1" Iron Bar
West 23.1 feet to a 2" Pipe in Road Bed
S45W 71.1 feet to a nail in a 24" Maple
S10E 28.9 feet to a nail in a Fence Post
N50W 38.5 feet to a nail in a Fence Post
West 2645.33 to the S 1/4 Cor
East 2642.28 to the S 1/4 Cor | L - 13
S 1/4 Cor Section 36 T13N-R13E
5/8" Iron Bar
West 15.88 to a 1/2" Iron Bar in gravel road bed
North 25.30 to a nail in a Fence Post
North 51.85 to a nail in a Tele Post
S15W 70.2 to a nail in a Power Pole
N70E 45.15 to a nail in a Black Cherry
West 2642.28 to the SW Cor
East 2633.66 to the SE Cor |
|--|---|

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date April 10, 96

